Quotation No : Q24000180

Date : 01-Apr-2024

Tamari Group
Damascus
MANESAR
HARYANA

Kind Attention : Mr./Ms. Abdulrhman Tamari

Dear Sir,

We understand that in industry, reliability is not just a requirement,it is the foundation of success.
That is why Absstem Industrial PSA Generator is more than just a product; it is a commitment to excellence, efficiency, and uninterrupted performance.

Every component is designed with precision and innovation, ensuring that each molecule of oxygen and nitrogen is delivered with the utmost purity.

With fully automated operation, our system seamlessly integrates into your processes, reducing manual intervention and maximizing productivity.

Moreover, our industry-leading air ratio ensures that you achieve the highest efficiency, optimizing energy consumption while maintaining peak performance.
And because we believe in standing by our craftsmanship, we offer an unmatched-10 year warranty on sieves, giving you the peace of mind that your investment is protected for the long run.

We have attached the detailed quotation for your review.

Should you have any questions or require further customization to meet your specific needs, please do not hesitate to reach out.

We are here to provide not just a product but a solution that breathes life into your operations.

We look forward to the opportunity to serve you and build a lasting partnership.

Thanks and Regards,

For Absstem Industrial Solutions Pvt. Ltd.

Arifa Zaidi
Assistant Manager Business Development
9218108184
www.absstem.com

Product Description

Product	Description	Make	Qty
HP Booster	MOC 100 AW- 200 BARG Booster	ABSSTEM	1

Caption	Specification
Gas to be compressed	Nitrogen
Suction Pressure	5 Barg
Discharge pressure	200 Barg
Motor rating	45 KW
Voltage	415 VAC
Gas Flow	100 Nm3/hr
Cooling Type	Air-water combi cooling

Product	Description	Make	Qty
HP Booster	MOC 100 W Booster	ABSSTEM	1

Caption	Specification
Gas to be compressed	Oxygen/Nitrogen
Suction Pressure	3 to 4 Barg
Discharge pressure	150 Barg
Motor rating	30 KW
Voltage	415 V AC
Gas Flow	100 NM3/hr
Type	Water cooled Oil Free Reciprocating Booster

Absstem Industrial Solutions Pvt. Ltd.
Ground Floor, Plot No. 591, Sector 8, Phase IV
IMT Manesar, Gurugram, Haryana - 122052
Contact: 1800 547 0506 | indsales@absstem.com
CIN: U29256HR2022PTC103387

Product	Description	Make	Qty
LP Booster 20 Barg	MOC 15 LP 20 Barg Booster	ABSSTEM	1

Caption	Specification
Gas to be compressed	Oxygen/Nitrogen
Suction Pressure	4 to 5 Barg
Discharge pressure	15 to 20 Barg
Voltage	415 V AC
Gas Flow	15 NM3/hr
Type	Air Cooled Oil Free Reciprocating Booster
Input Power	4 KW

Product	Description	Make	Qty
HP Storage Tank 20 Barg	1500 ltr HP Storage Tank 20 Barg High Pressure Storage Tank	ABSSTEM	1

Caption	Specification
Capacity	1500 litres
Working Pressure	20 Barg
Hydrotest Pressure	33 Barg
Shell / Dish Thickness	14 mm / 16 mm
In / Out Connection	1-1/2" BSPF
Design Standard	IS 2825

Commercial Offer

S No	Item Code	Item Name	Description	HSN	Qty	Unit Price	GST(%)	Amount
1	MOC 100 AW-200 BARG	MOC 100 AW-200 BARG	HP Booster	8414	1	90,00,000.00	18.00	90,00,000.00
2	MOC 100 W-1	MOC 100 W	HP Booster	8414	1	51,82,365.60	18.00	51,82,365.60
3	BC2	MOC 15 LP 20 Barg	LP Booster 20 Barg	84144030	1	7,98,000.00	18.00	7,98,000.00
4	HPS4	1500 ltr HP Storage Tank 20 Barg	HP Storage Tank 20 Barg	73110090	1	2,75,880.00	18.00	2,75,880.00
							Sub Total	1,52,56,245.60

Absstem Industrial Solutions Pvt. Ltd.
Ground Floor, Plot No. 591, Sector 8, Phase IV
IMT Manesar, Gurugram, Haryana - 122052
Contact: 1800 547 0506 | indsales@absstem.com
CIN: U29256HR2022PTC103387

GST(%) @18.00	27,46,124.21
Grand Total ()	1,80,02,369.81

Terms And Conditions

1.	EXCLUSIONS & CLIENTS SCOPE	All erection / civil work, All Power Cables & Cabling out of battery limit of PSA Plant, Cable Trenches etc. Unloading / Shifting of Gas Plant at Clients site will be in Client Scope. Additional gas piping, cooling water (if required).
2.	SUPERVISION OF ERECTION & COMMISSIONING	There shall be no commissioning charges, however you shall arrange freeTo & Fro Air Ticket, lodging / boarding, and local conveyance for our Engineers during supervision of Installation of Gas Plant at site on free of cost basis. Our Engineers will be there for Supervision only. Any manpower / fitter required for installation work shall be provided by you.
3.	P&F	3% Extra.
4.	Freight	Extra at Actuals.
5.	Insurance	In your Scope.
6.	Payment Terms	50% Advance with your Prestegious Purchase Order and Balance against PI.
7.	Delivery	6-8 Weeks from the PO and Advance. Rest can be confirmed for Availability.
8.	Warranty	We hereby confirm that, our equipment shall have Suppliers warranty for a period of 12 months from the date of Commissioning or 18 months from date of Dispatch whichever is earlier.
9.	GST	As per the Commercial Table.
10.	Remarks	.
11.	Absstem GST Details	06AAWCA9492P1ZF - ABSSTEM INDUSTRIAL SOLUTIONS PRIVATE LIMITED

Hope you will find our offer in line with your requirement.

Should you require any further clarification/information, please feel free to contact us.

Thanking you, and assuring you of our best attention at all times.

Very Yours truly,

For Absstem Industrial Solutions Pvt. Ltd.

Arifa Zaidi

Assistant Manager Business Development

9218108184

www.absstem.com