Assam Bearing Private Limited
2423 Surekha Building, Shardhanand marg, Delhi-110006
GSTN-07AADCA3768K1ZF
www.Assambearing.in
Ph: +91-9350193013, Email: Delhi@assambearing.com

Quotation No : Q25000467

Date : 05-Dec-2025

UNO MINDA LIMITED
Village Naharpur Kasan, PO. Nakhrola
MANESAR
HARYANA
122050

Kind Attention : Mr./Ms. Suyog Chavan

Dear Sir,
Greetings from Assam Bearing

We are Authorized Distributors of SKF Bearings, Red Lion, Lincoln Lubrication Systems, Fuchs Lubricants & Absstem Industrial Solutions.

We are dealing with various industrial products such as:
-Bearings, Greases, Chain, Sprockets, Pulleys, V-Belts, Oil seals
-Lubrication Systems
-Condition Monitoring, Energy Monitoring Solutions, IIoT Solutions
-Industrial Lubricants
-Nitrogen & Oxygen Air Generator

Our team understands that selecting gas generation systems is a difficult task.

We have the expertise to help you, being a prime Distributor and supplier of Absstem gas generation systems.

Absstem has the resources, facilities, technology, and expertise required to ensure a successful project.

Post-installation, their shield service division, with diligent accuracy and functionality, oversees a team of technicians who provide warranty and post-warranty support to your newly installed gas generation systems.
Our products have consistently delivered absolute purity requirements.
The industry is lowest ever production downtime.

Reduce OPEX by at least 70 %
We wish to form a long-term relationship with the goal of developing the most cost effective and comprehensive solutions for your needs and are thus submitting our offer along with ROI calculation from our side, hope you will find our offer in accordance with your requirements & will be more than happy to serve your requirements, please call us for any queries.

For Assam Bearing Pvt Ltd.

Shray Saboo

Director

9350193012



nGEN POWERED BY ABSSTEM INDUSTRIAL

Industrial

PSA Nitrogen Generator

Unique Features of Absstem Nitrogen Generator nGEN UH

a. **Lowest Air to Gas ratio** in industry thereby guaranteeing **lowest power consumption**.
b. **10 years*** warranty on Molecular Sieves **(First In Industry)**.
c. Assured Performance for consistent Flow, Pressure and Purity of Nitrogen throughout Product Lifecycle.
d. IIOT ready machine having 100% operator free design for 24X7 operation.
e. Idle mode with auto start/stop features ensuring power savings during low/no demand.
f. Inbuilt dew point transmitter to monitor input compressed air quality as standard scope of supply.
g. Plug n Play machine with an ergonomic design suitable for accessibility.
h. All the Instruments are specially manufactured to make them suitable for Nitrogen gas.
i. All critical performance parameters are being monitored through HMI.
j. First in industry **Comprehensive Maintenance Contract (CMC)** service under Absstem Premium Shield program providing complete peace of mind to customer.

Ambient Design Parameters

a.	Temperature	0 to 45 Deg. Celsius
b.	Relative Humidity	up to 80 % (Max.)
c.	Altitude	up to 1000 m above Sea level

Absstem Industrial Solutions Pvt. Ltd.
Plot No. 591, Sector 8, Phase IV
IMT Manesar, Gurugram, Haryana - 122051
Contact - 1800 3010 3394 Email - indsales@absstem.com
CIN: U29256HR2022PTC103387

Product Description

a. Product Name	Ultra Purity PSA Nitrogen Gas Generator
b. PSA Module	**nGEN UH**
c. Purity Range	99.99% - 99.999%

General PSA Generation System Layout

A typical Industrial Nitrogen Generation system consists of three parts:

- Compressed Air System: Air Compressor, Pre-filter, Air Dryer, Dry Air Vessel
- PSA N_2 Generation System
- N_2 Storage Tank



Air Compressor	An Air compressor is used to compress the atmospheric air to a pressure required for the separation of **Nitrogen** from the air.
Refrigeration dryer	Compressed air then passes through a refrigerated dryer to remove moisture (which is harmful to sieves) from the air.
Air Tank	Dry air is collected in an air tank to remove the pulsations which serve the dynamic (changing) requirement of air by the PSA system.
Multistage Filtration system	Before air enters the PSA system, it is passed through multistage filtration removing moisture, particulates and oil content to the specified levels.
PSA system	Pressurized air is passed through PSA Towers filled with Molecular sieves to separate **Nitrogen** from Air.
Storage Tank	Industrial Grade **Nitrogen** produced from the PSA System is stored in this for continuous supply.
Oxygen Analyser	Nitrogen produced is monitored by an Oxygen analyser. In case, O_2 impurity goes above the specified level, it gives an alarm and switches the plant to vent mode.

Absstem Industrial Solutions Pvt. Ltd.
Plot No. 591, Sector 8, Phase IV
IMT Manesar, Gurugram, Haryana - 122051
Contact - 1800 3010 3394 Email - indsales@absstem.com
CIN: U29256HR2022PTC103387

HD Touch Screen Display

(User-friendly touch screen interface for easy operation and maintenance)

Absstem industrial Nitrogen generators complies with all industry standards and regulation

- Alarm management system
- Process data display
- Consumables running hours' display
- Data logging via USB drive**
- Graphical representation**



Additional upgrades

- Digital flow meter with totalizer
- Nitrogen Pressure monitoring for High pressure booster driven plants
- Cylinder manifold and alarm management system
- Remote monitoring
- Nitrogen gas Dew-point monitoring

International Quality standards

A strict quality procedure, following the leading international pharmacopoeia and Industrial directives, is followed in the selection of all mechanical and electrical instruments, vessel fabrication and designing of Industrial Gas generators.

TÜV NORD ISO 9001 · TÜV NORD ISO 14001 · TÜV NORD ISO 13485 · RIR CERTIFICATION Partners in Growth

Absstem Industrial Solutions Pvt. Ltd.
Plot No. 591, Sector 8, Phase IV
IMT Manesar, Gurugram, Haryana - 122051
Contact - 1800 3010 3394 Email - indsales@absstem.com
CIN: U29256HR2022PTC103387

Absstem Shield Premium

(Comprehensive Annual Maintenance Contract)



Any Industry is now heavily focused on increased OEE (Overall Equipment Efficiency) and reduced LCC (Life Cycle Cost) while deciding to invest in any equipment. At Absstem, we strive for an everlasting engagement with our customers by not selling them just a product but also provide a long term after-sales support.

We understand that to deliver a consistent performance, periodic health check and timely maintenance of the Nitrogen Generator is extremely important. With Absstem Shield Premium, you invest in complete peace of mind for all maintenance needs pertaining to N2 generators and associated integrated equipment like air compressor, Air dryer etc.

Few benefits of Absstem Shield Premium are listed as below: -

- Guaranteed assurance of plant performance.
- Genuine spare parts and consumables being used to provide longevity and durability.
- Regular visits by our technicians for health monitoring and carrying out the scheduled maintenance services.
- 24 x 7 On-Call service support to our customers for any basic trouble shooting
- Emergency visit to attend any unplanned breakdown to any location within 48 hours.
- No additional surprise charges as all breakdown spares and consumables covered.
- The contract can be signed at the time of equipment ordering itself and can be renewed on year on year basis.

Absstem Industrial Solutions Pvt. Ltd.
Plot No. 591, Sector 8, Phase IV
IMT Manesar, Gurugram, Haryana - 122051
Contact - 1800 3010 3394 Email - indsales@absstem.com
CIN: U29256HR2022PTC103387

Assam Bearing Private Limited
2423 Surekha Building, Shardhanand marg, Delhi-110006
GSTN-07AADCA3768K1ZF
www.Assambearing.in
Ph: +91-9350193013, Email: Delhi@assambearing.com

www.assambearing.in

Product Description

Product	Description	Make	Qty
Compressed Air System	C090F0600 Air System		1

Caption	Specification
Air Compressor KW	90 KW
Air Compressor Make	Atlas Copco/ Ingersoll Rand/ Gardner Denver/ As per Demand
Air Dryer	Included
Dry Air Storage	5000 Liters Included
Interconnecting Piping	Included
Pre filter	Included
Dry Air Generated	602 CFM
Air Pressure	7.5 Barg
POWER SUPPLY	400 V 3 Phase 50 Hz

Product	Description	Make	Qty
nGen Nitrogen Generator Ultra Purity	nGEN115UH Nitrogen		1

Caption	Specification
Gas Generated	Nitrogen
Gas Pressure	upto 6.5 Barg
FLOW AT 99.99% PURITY	190 Nm3/Hr DRY AIR REQUIRED 537 CFM
FLOW AT 99.995% PURITY	170 Nm3/Hr DRY AIR REQUIRED 602 CFM
FLOW AT 99.999% PURITY	128 Nm3/Hr DRY AIR REQUIRED 603 CFM
COMPRESSED AIR PRESSURE REQUIRED	7.5 Barg
RECOMMENDED NITROGEN STORAGE	4000 Liters
POWER SUPPLY	230 V/ 110 V 50/60 Hz Single Phase
RECOMMENDED AIR RECEIVER	5000 Litres Part of Air System
INPUT AIR DEW POINT MONITOR	INCLUDED
CMS Warranty	10 Years*

Assam Bearing Private Limited
2423 Surekha Building, Shardhanand marg, Delhi-110006
GSTN-07AADCA3768K1ZF
www.Assambearing.in
Ph: +91-9350193013, Email: Delhi@assambearing.com

Product	Description	Make	Qty
Gas Storage Vessel	AI-4000L Storage Vessel		1

Caption	Specification
Water Volume	4000 Litres
Gas Stored	Nitrogen/Oxygen
Design Standard	ASME Sec. VIII Div.1 Pressure Vessel Design
Working Pressure	8 Barg
Hydrotest Pressure	13.2 Barg
Accessories Included	Pressure Guage Safety Valve Manual Drain Additional Port for Other Instruments
Material of Construction	IS2062 Gr.B
Gas Stored Volume	26 M3
Corrosion Allowance	1.5 MM

Commercial Offer

S No	Item Code	Item Name	Description	HSN	Qty	Unit Price	GST(%)	Amount
1	ACSC090F	C090F0600	Compressed Air System	840510	1	34,15,000.00	18.00	34,15,000.00
2	nGEN115UH	nGEN115UH	nGen Nitrogen Generator Ultra Purity	840510	1	86,06,000.00	18.00	86,06,000.00
3	AIS0408ST	AI-4000L	Gas Storage Vessel	731100	1	2,80,000.00	18.00	2,80,000.00
							Sub Total	1,23,01,000.00
							GST(%) @18.00	22,14,180.00
							Grand Total	1,45,15,180.00

Assam Bearing Private Limited
2423 Surekha Building, Shardhanand marg, Delhi-110006
GSTN-07AADCA3768K1ZF
www.Assambearing.in
Ph: +91-9350193013, Email: Delhi@assambearing.com

Terms And Conditions

1.	EXCLUSIONS & CLIENTS SCOPE	All erection / civil work, All Power Cables & Cabling out of battery limit of PSA Plant, Cable Trenches etc. Unloading / Shifting of Gas Plant at Clients site will be in Client Scope. Additional gas piping, cooling water (if required).
2.	SUPERVISION OF ERECTION & COMMISSIONING	There shall be no commissioning charges, however you shall arrange freeTo & Fro Air Ticket, lodging / boarding, and local conveyance for our Engineers during supervision of Installation of Gas Plant at site on free of cost basis. Our Engineers will be there for Supervision only. Any manpower / fitter required for installation work shall be provided by you.
3.	P&F	3% Extra.
4.	Freight	Extra at Actuals.
5.	Insurance	In your Scope.
6.	Payment Terms	50% Advance with your Prestegious Purchase Order and Balance against PI.
7.	Delivery	6-8 Weeks from the PO and Advance. Rest can be confirmed for Availability.
8.	Warranty	We hereby confirm that, our equipment shall have Suppliers warranty for a period of 12 months from the date of Commissioning or 18 months from date of Dispatch whichever is earlier.
9.	GST	As per the Commercial Table.
10.	Remarks	.

Hope you will find our offer in line with your requirement.

Should you require any further clarification/information, please feel free to contact us.

Thanking you, and assuring you of our best attention at all times.

Very Yours truly,

For Assam Bearing Pvt Ltd.

Shray Saboo

Director

9350193012

www.assambearing.in