Quotation No : Q26000343

Date : 23-Jun-2026

Dr. Nitin Ranjan
IIT Delhi
NEW DELHI
DELHI

Kind Attention : Mr./Ms. Dr. Nitin Ranjan

Dear Sir,

We understand that in industry, reliability is not just a requirement,it is the foundation of success.
That is why Absstem Industrial PSA Generator is more than just a product; it is a commitment to excellence, efficiency, and uninterrupted performance.

Every component is designed with precision and innovation, ensuring that each molecule of oxygen and nitrogen is delivered with the utmost purity.

With fully automated operation, our system seamlessly integrates into your processes, reducing manual intervention and maximizing productivity.

Moreover, our industry-leading air ratio ensures that you achieve the highest efficiency, optimizing energy consumption while maintaining peak performance.
And because we believe in standing by our craftsmanship, we offer an unmatched-10 year warranty on sieves, giving you the peace of mind that your investment is protected for the long run.

We have attached the detailed quotation for your review.

Should you have any questions or require further customization to meet your specific needs, please do not hesitate to reach out.

We are here to provide not just a product but a solution that breathes life into your operations.

We look forward to the opportunity to serve you and build a lasting partnership.

Thanks and Regards,

For Absstem Industrial Solutions Pvt. Ltd.

Arifa Zaidi
Assistant Manager Business Development
9218108184
www.absstem.com

Product Description

Product	Description	Make	Qty
IDOS C	IDOS 12.5C Oxygen		3

Caption	Specification
Gas Generated	Oxygen
Flow	12.5 Nm3/Hr
Purity	95 Percent
Compressor	In Your Scope / Quoted Separately
Dryer	In Your Scope / Part of Compressor Package
Air Vessel	In Your Scope / Part of Compressor Package
Dry Air Required	101 CFM
Power Required	230V 50 Hz Single Phase
Module Option	PSA Plant Only

Product	Description	Make	Qty
IDOS Gas Storage	IDOS 12.5 ST Oxygen		3

Caption	Specification
Water Volume	2500 Litres
Gas Stored	Oxygen
Gas Stored Volume	13.75 M3
Working Pressure	5.5 Barg
Hydrotest Pressure	9 Barg

Commercial Offer

S No	Item Code	Item Name	Description	HSN	Qty	Unit Price	Discount	GST(%)	Amount
1	IDOS 12.5C	IDOS 12.5C	IDOS C	842139	3	15,70,800.00	3,53,430.00	18.00	36,52,110.00
2	IDOS 12.5 ST	IDOS 12.5 ST	IDOS Gas Storage	842139	3	2,28,000.00	51,300.00	18.00	5,30,100.00
								Sub Total	41,82,210.00

Absstem Industrial Solutions Pvt. Ltd.
Ground Floor, Plot No. 591, Sector 8, Phase IV
IMT Manesar, Gurugram, Haryana - 122052
Contact: 1800 547 0506 | indsales@absstem.com
CIN: U29256HR2022PTC103387

GST(%) @18.00	7,52,797.80
Grand Total (INR)	49,35,008.00

Terms And Conditions

1.	EXCLUSIONS & CLIENTS SCOPE	All erection / civil work, All Power Cables & Cabling out of battery limit of PSA Plant, Cable Trenches etc. Unloading / Shifting of Gas Plant at Clients site will be in Client Scope. Additional gas piping, cooling water (if required).
2.	SUPERVISION OF ERECTION & COMMISSIONING	There shall be no commissioning charges, however you shall arrange freeTo & Fro Air Ticket, lodging / boarding, and local conveyance for our Engineers during supervision of Installation of Gas Plant at site on free of cost basis. Our Engineers will be there for Supervision only. Any manpower / fitter required for installation work shall be provided by you.
3.	P&F	In the spirit of institutional partnership, we agree to subsidize our standard Packing & Forwarding charges by 50%, capturing them at 1.5%. However, because safely transporting three multi-skid industrial gas plants across state lines requires dedicated Full Truckload (FTL) transit.
4.	Freight	Extra at Actuals.
5.	Insurance	In your Scope.
6.	Payment Terms	Advance - Nil, 100% of applicable GST payable upon readiness of the machines at our factory and balance by January 2027.
7.	Delivery	We accept the frozen site delivery target of 15 August 2026, strictly subject to the formal Purchase Order being received at our works no later than 4 July 2026. Because our standard manufacturing and testing lead time is 6 weeks, any delay in receipt of the PO beyond 4 July 2026 will necessarily shift delivery to
8.	Warranty	We expressly incorporate the 10-year warranty on molecular sieves into the binding commercial terms. We also accept extending the equipment warranty to 24 months from commissioning or 30 months from dispatch, whichever is later.
9.	GST	As per the Commercial Table.
10.	Remarks	Comprehensive Maintenance Contract (CMC) Charges: INR 160,000 + GST per year for each PSA Oxygen Plant.

Hope you will find our offer in line with your requirement.

Should you require any further clarification/information, please feel free to contact us.

Thanking you, and assuring you of our best attention at all times.

Very Yours truly,

For Absstem Industrial Solutions Pvt. Ltd.

Arifa Zaidi
Assistant Manager Business Development
9218108184
www.absstem.com