Sales Order No : S25000089

Sale Order Date : 04-Jul-2025

Job No :
N075,N075,N075,N075,N075,N075,N075,N075,N075,N075,N075,N075,N075,N075,N075,N075

Customer Information

Sales Person : Pramod Kumar

Subros Limited

Mobile

Yogesh Panchal

Consignee Details :

Pune

Subros Limited

MAHARASHTRA

Pune

PUNE

MAHARASHTRA

yogesh.panchal@subros.com

PUNE

Performance

Product	Description	Make	Qty
Lubricated Booster	IR-15T2X20 Booster	ABSSTEM	1

Caption	Specification
Gas to be compressed	Nitrogen
Suction Pressure	3 to 4 Barg
Discharge pressure	8 to 70 Barg
Motor rating	15 KW
Voltage	415 V AC
Gas Flow	51 to 62 NM3/hr
Type	Air Cooled Lubricated Reciprocating Booster
Volume	1000 litres
Working Pressure	65 Barg
Hydrotest Pressure	107.25 Barg
Water Volume	1000 Litres
Gas Stored	Nitrogen/Oxygen
Design Standard	ASME Sec. VIII Div.1 Pressure Vessel Design
Working Pressure	8 Barg
Hydrotest Pressure	13.2 Barg
Accessories Included	Pressure Guage Safety Valve Manual Drain Additional Port for Other Instruments
Material of Construction	IS2062 Gr.B
Gas Stored Volume	6.5 M3
Corrosion Allowance	1.5 MM
Water Volume	500 Litres
Gas Stored	Nitrogen/Oxygen

Design Standard	ASME Sec. VIII Div.1 Pressure Vessel Design
Working Pressure	8 Barg
Hydrotest Pressure	13.2 Barg
Accessories Included	Pressure Guage Safety Valve Manual Drain Additional Port for Other Instruments
Material of Construction	IS2062 Gr.B
Gas Stored Volume	3.25 M3
Corrosion Allowance	1.5 MM
Gas Generated	Nitrogen
Gas Pressure	upto 6.5 Barg
FLOW AT 99% PURITY	73 Nm3/Hr DRY AIR REQUIRED 95 CFM
FLOW AT 99.5% PURITY	61 Nm3/Hr DRY AIR REQUIRED 92 CFM
FLOW AT 99.9% PURITY	45 Nm3/Hr DRY AIR REQUIRED 85 CFM
FLOW AT 99.95% PURITY	41 Nm3/Hr DRY AIR REQUIRED 90 CFM
COMPRESSED AIR PRESSURE REQUIRED	7.5 Barg
RECOMMENDED NITROGEN STORAGE	1500 Liters
POWER SUPPLY	230 V/ 110 V 50/60 Hz Single Phase
RECOMMENDED AIR RECEIVER	1000 Litres Part of Air System
INPUT AIR DEW POINT MONITOR	INCLUDED
CMS Warranty	10 Years*
Air Compressor KW	15 KW
Air Compressor Make	Atlas Copco/ Ingersoll Rand/ Gardner Denver/ As per Demand
Air Dryer	Included
Dry Air Storage	700 Liters Included
Interconnecting Piping	Included
Pre filter	Included
Dry Air Generated	94 CFM
Air Pressure	7.5 Barg
POWER SUPPLY	400 V 3 Phase 50 Hz
Water Volume	2000 Litres
Gas Stored	Nitrogen/Oxygen
Design Standard	ASME Sec. VIII Div.1 Pressure Vessel Design
Working Pressure	8 Barg
Hydrotest Pressure	13.2 Barg
Accessories Included	Pressure Guage Safety Valve Manual Drain Additional Port for Other Instruments
Material of Construction	IS2062 Gr.B
Gas Stored Volume	13 M3
Corrosion Allowance	1.5 MM
SO Remarks	Recovery Cum Generation Package included power panel etc.

Absstem Industrial Solutions Pvt. Ltd.
Ground Floor, Plot No. 591, Sector 8, Phase IV
IMT Manesar, Gurugram, Haryana - 122052
Contact: 1800 547 0506 | indsales@absstem.com
CIN: U29256HR2022PTC103387

Final Remarks	This will be a skid based design with internal piping of all skid to be done inhouse and piping between the skid will be at site

absstem REINVENTING PERFORMANCE

Absstem Industrial Solutions Pvt. Ltd.
Ground Floor, Plot No. 591, Sector 8, Phase IV
IMT Manesar, Gurugram, Haryana - 122052
Contact: 1800 547 0506 | indsales@absstem.com
CIN: U29256HR2022PTC103387

Commercial Offer

S No	Item Code	Item Name	Qty	List Price	Discount	GST(%)	Amount
1	ASH74	Vacuum Blower	1	3,67,500.00	1,17,500.00	18.00	2,50,000.00
2	ASH155	15TNLX125PSI 20HP	1	9,60,000.00	3,60,000.00	18.00	6,00,000.00
3	IR-15T2X20	IR-15T2X20	1	7,80,000.00	3,50,000.00	18.00	4,30,000.00
4	HPS15	1000 ltr HP Storage Tank 65 Barg	1	5,40,000.00	2,15,000.00	18.00	3,25,000.00
5	ASH310	Refrigerent Dryer 1M3	1	1,44,000.00	64,000.00	18.00	80,000.00
6	AIS0108ST	AI-1000L	2	1,20,000.00	90,000.00	18.00	1,50,000.00
7	AIS0058ST	AI-500L	1	72,000.00	24,000.00	18.00	48,000.00
8	ASH311	Low Pressure and high Pressure Pipeline	1	2,40,000.00	1,50,000.00	18.00	90,000.00
9	nGEN020SH	nGEN020SH	1	22,59,600.00	11,69,600.00	18.00	10,90,000.00
10	ACSC015F	C015F0094	1	9,84,000.00	3,36,000.00	18.00	6,48,000.00
11	AIS0208ST	AI-2000L	1	1,92,000.00	82,000.00	18.00	1,10,000.00
12	ASH312	Heat Exchanger for 1m3 Capacity	1	48,000.00	8,000.00	18.00	40,000.00
13	ASH313	VFD 5 KW Auto	1	36,000.00	11,000.00	18.00	25,000.00
14	ASH314	Pressure Reducing Station	1	1,20,000.00	50,000.00	18.00	70,000.00
15	ASH220	FILTER FOR HIGH PRESSURE	1	1,20,000.00	35,000.00	18.00	85,000.00
16	ASH60	N2 Mass Flow Meter	1	2,10,000.00	1,01,000.00	18.00	1,09,000.00
						Sub Total	41,50,000.00
						IGST	7,47,000.00
						Net Amount ()	48,97,000.00

Absstem Industrial Solutions Pvt. Ltd.
Ground Floor, Plot No. 591, Sector 8, Phase IV
IMT Manesar, Gurugram, Haryana - 122052
Contact: 1800 547 0506 | indsales@absstem.com
CIN: U29256HR2022PTC103387

Terms And Conditions

1. Freight	Included
2. Payment Terms	50% Advance with your Prestegious Purchase Order and 40% against PI before dispatch and balance after installation and commissioning
3. Delivery	4-6 Weeks from the PO and Advance. Rest can be confirmed for Availability
4. Freight Scope	Absstem
5. Insurance Scope	Absstem
6. Installation and commissioning Engineer	Stay - Absstem, Food - Absstem, Travel - Absstem
7. Committed date of Delivery	1st week of August
8. Scope of Supply	Type of Plant - Nitrogen Recovery Cum Generation, Purity-99.95, Flow - 45 Nm3/hr, Pressure- 65 Barg

Absstem Industrial Solutions Pvt. Ltd.
Ground Floor, Plot No. 591, Sector 8, Phase IV
IMT Manesar, Gurugram, Haryana - 122052
Contact: 1800 547 0506 | indsales@absstem.com
CIN: U29256HR2022PTC103387