Sales Order No : S25000090

Sale Order Date : 07-Jul-2025

Job No :
N076,N076,N076,N076,N076,N076,N076,N076,N076,N076,N076,N076,N076,N076,N076,N076

Customer Information

Sales Person : Pramod Kumar

Subros Limited

Mobile

Vinoth Kumar

Consignee Details :

A20/1 SIPCOT,Indl GrowthCentre, Sriperumbudur Post, Kancheepuram

Subros Limited

TAMILNADU

A20/1 SIPCOT,Indl GrowthCentre, Sriperumbudur Post, Kancheepuram

Chennai

TAMILNADU

vinothkumar.t@subros.com

Chennai

## Performance

| Product | Description | Make | Qty |
|---|---|---|---|
| Lubricated Booster | IR-15T2X20 Booster | ABSSTEM | 1 |

| Caption | Specification |
|---|---|
| Gas to be compressed | Nitrogen |
| Suction Pressure | 3 to 4 Barg |
| Discharge pressure | 8 to 70 Barg |
| Motor rating | 15 KW |
| Voltage | 415 V AC |
| Gas Flow | 51 to 62 NM3/hr |
| Type | Air Cooled Lubricated Reciprocating Booster |
| Volume | 1000 litres |
| Working Pressure | 65 Barg |
| Hydrotest Pressure | 107.25 Barg |
| Water Volume | 1000 Litres |
| Gas Stored | Nitrogen/Oxygen |
| Design Standard | ASME Sec. VIII Div.1 Pressure Vessel Design |
| Working Pressure | 8 Barg |
| Hydrotest Pressure | 13.2 Barg |
| Accessories Included | Pressure Guage Safety Valve Manual Drain Additional Port for Other Instruments |
| Material of Construction | IS2062 Gr.B |
| Gas Stored Volume | 6.5 M3 |
| Corrosion Allowance | 1.5 MM |
| Water Volume | 500 Litres |

| | |
|---|---|
| Gas Stored | Nitrogen/Oxygen |
| Design Standard | ASME Sec. VIII Div.1 Pressure Vessel Design |
| Working Pressure | 8 Barg |
| Hydrotest Pressure | 13.2 Barg |
| Accessories Included | Pressure Guage Safety Valve Manual Drain Additional Port for Other Instruments |
| Material of Construction | IS2062 Gr.B |
| Gas Stored Volume | 3.25 M3 |
| Corrosion Allowance | 1.5 MM |
| Gas Generated | Nitrogen |
| Gas Pressure | upto 6.5 Barg |
| FLOW AT 99% PURITY | 46 Nm3/Hr DRY AIR REQUIRED 60 CFM |
| FLOW AT 99.5% PURITY | 39 Nm3/Hr DRY AIR REQUIRED 59 CFM |
| FLOW AT 99.9% PURITY | 29 Nm3/Hr DRY AIR REQUIRED 55 CFM |
| FLOW AT 99.95% PURITY | 26 Nm3/Hr DRY AIR REQUIRED 57 CFM |
| COMPRESSED AIR PRESSURE REQUIRED | 7.5 Barg |
| RECOMMENDED NITROGEN STORAGE | 1000 Liters |
| POWER SUPPLY | 230 V/ 110 V 50/60 Hz Single Phase |
| RECOMMENDED AIR RECEIVER | 500 Litres Part of Air System |
| INPUT AIR DEW POINT MONITOR | INCLUDED |
| CMS Warranty | 10 Years* |
| Air Compressor KW | 15 KW |
| Air Compressor Make | Atlas Copco/ Ingersoll Rand/ Gardner Denver/ As per Demand |
| Air Dryer | Included |
| Dry Air Storage | 700 Liters Included |
| Interconnecting Piping | Included |
| Pre filter | Included |
| Dry Air Generated | 94 CFM |
| Air Pressure | 7.5 Barg |
| POWER SUPPLY | 400 V 3 Phase 50 Hz |
| Water Volume | 2000 Litres |
| Gas Stored | Nitrogen/Oxygen |
| Design Standard | ASME Sec. VIII Div.1 Pressure Vessel Design |
| Working Pressure | 8 Barg |
| Hydrotest Pressure | 13.2 Barg |
| Accessories Included | Pressure Guage Safety Valve Manual Drain Additional Port for Other Instruments |
| Material of Construction | IS2062 Gr.B |
| Gas Stored Volume | 13 M3 |
| Corrosion Allowance | 1.5 MM |
| SO Remarks | Nitrogen recovery cum generation package including power panel etc. |



**Absstem Industrial Solutions Pvt. Ltd.**
Ground Floor, Plot No. 591, Sector 8, Phase IV
IMT Manesar, Gurugram, Haryana - 122052
**Contact**: 1800 547 0506 | indsales@absstem.com
**CIN**: U29256HR2022PTC103387

| | |
|---|---|
| Final Remarks | non standard job |

**Absstem Industrial Solutions Pvt. Ltd.**
Ground Floor, Plot No. 591, Sector 8, Phase IV
IMT Manesar, Gurugram, Haryana - 122052
**Contact**: 1800 547 0506 | indsales@absstem.com
**CIN**: U29256HR2022PTC103387

# Commercial Offer

| S No | Item Code | Item Name | Qty | List Price | Discount | GST(%) | Amount |
|---|---|---|---|---|---|---|---|
| 1 | ASH74 | Vacuum Blower | 1 | 3,06,250.00 | 56,250.00 | 18.00 | 2,50,000.00 |
| 2 | ASH155 | 15TNLX125PSI 20HP | 1 | 8,00,000.00 | 2,00,000.00 | 18.00 | 6,00,000.00 |
| 3 | IR-15T2X20 | IR-15T2X20 | 1 | 6,50,000.00 | 2,20,000.00 | 18.00 | 4,30,000.00 |
| 4 | HPS15 | 1000 ltr HP Storage Tank 65 Barg | 1 | 4,50,000.00 | 1,25,000.00 | 18.00 | 3,25,000.00 |
| 5 | ASH310 | Refrigerent Dryer 1M3 | 1 | 1,20,000.00 | 40,000.00 | 18.00 | 80,000.00 |
| 6 | AIS0108ST | AI-1000L | 2 | 1,00,000.00 | 25,000.00 | 18.00 | 1,50,000.00 |
| 7 | AIS0058ST | AI-500L | 1 | 60,000.00 | 12,000.00 | 18.00 | 48,000.00 |
| 8 | ASH311 | Low Pressure and high Pressure Pipeline | 1 | 2,00,000.00 | 1,10,000.00 | 18.00 | 90,000.00 |
| 9 | nGEN010SH | nGEN010SH | 1 | 11,48,000.00 | 1,05,000.00 | 18.00 | 10,43,000.00 |
| 10 | ACSC015F | C015F0094 | 1 | 8,20,000.00 | 2,14,000.00 | 18.00 | 6,06,000.00 |
| 11 | AIS0208ST | AI-2000L | 1 | 1,60,000.00 | 50,000.00 | 18.00 | 1,10,000.00 |
| 12 | ASH312 | Heat Exchanger for 1m3 Capacity | 1 | 40,000.00 | | 18.00 | 40,000.00 |
| 13 | ASH313 | VFD 5 KW Auto | 1 | 30,000.00 | 5,000.00 | 18.00 | 25,000.00 |
| 14 | ASH314 | Pressure Reducing Station | 1 | 1,00,000.00 | 30,000.00 | 18.00 | 70,000.00 |
| 15 | ASH220 | FILTER FOR HIGH PRESSURE | 1 | 1,00,000.00 | 15,000.00 | 18.00 | 85,000.00 |
| 16 | ASH60 | N2 Mass Flow Meter | 2 | 1,75,000.00 | 66,000.00 | 18.00 | 2,18,000.00 |
| | | | | | | Sub Total | 41,70,000.00 |
| | | | | | | IGST | 7,50,600.00 |
| | | | | | | Net Amount () | 49,20,600.00 |



**Absstem Industrial Solutions Pvt. Ltd.**
Ground Floor, Plot No. 591, Sector 8, Phase IV
IMT Manesar, Gurugram, Haryana - 122052
**Contact**: 1800 547 0506 | indsales@absstem.com
**CIN**: U29256HR2022PTC103387

# Terms And Conditions

| | |
|---|---|
| 1. EXCLUSIONS & CLIENTS SCOPE | All erection / civil work, All Power Cables & Cabling out of battery limit of PSA Plant, Cable Trenches etc. Unloading / Shifting of Gas Plant at Clients site will be in Client Scope. Additional gas piping, cooling water (if required). |
| 2. Freight | Included |
| 3. Payment Terms | 50% Advance with your Prestegious Purchase Order and 40% against PI before dispatch and balance against installation and commissioning |
| 4. Delivery | 6-8 Weeks from the PO and Advance. Rest can be confirmed for Availability |
| 5. Warranty | We hereby confirm that, our equipment shall have Suppliers warranty for a period of 12 months from the date of Commissioning or 18 months from date of Dispatch whichever is earlier. |
| 6. Scope of Supply | Type of Plant - Nitrogen recovery cum generation, Purity-99.9%, Flow-30 Nm3/hr, Pressure-65 Barg |



**Absstem Industrial Solutions Pvt. Ltd.**
Ground Floor, Plot No. 591, Sector 8, Phase IV
IMT Manesar, Gurugram, Haryana - 122052
**Contact**: 1800 547 0506 | indsales@absstem.com
**CIN**: U29256HR2022PTC103387