Sales Order No : S25000106

Sale Order Date : 29-Aug-2025

Job No : N082,N082,N082,N082,N082,N082,N082,N082,N082,N082,N082,N082,N082,N082

Customer Information

Sales Person : Pramod Kumar

Subros Limited

Mobile

Amit Singal

Consignee Details :

8373+V4X, Karsanpura

Subros Limited

GUJARAT

8373+V4X, Karsanpura

AHMEDABAD

GUJARAT

amit.singal@subros.com

AHMEDABAD

## Performance

| Product | Description | Make | Qty |
|---|---|---|---|
| Lubricated Booster | IR-15T2X20 Booster | ABSSTEM | 3 |

| Caption | Specification |
|---|---|
| Gas to be compressed | Nitrogen |
| Suction Pressure | 3 to 4 Barg |
| Discharge pressure | 8 to 70 Barg |
| Motor rating | 15 KW |
| Voltage | 415 V AC |
| Gas Flow | 51 to 62 NM3/hr |
| Type | Air Cooled Lubricated Reciprocating Booster |
| Volume | 2000 litres |
| Working Pressure | 65 Barg |
| Hydrotest Pressure | 107.25 Barg |
| Water Volume | 2000 Litres |
| Gas Stored | Nitrogen/Oxygen |
| Design Standard | ASME Sec. VIII Div.1 Pressure Vessel Design |
| Working Pressure | 8 Barg |
| Hydrotest Pressure | 13.2 Barg |
| Accessories Included | Pressure Guage Safety Valve Manual Drain Additional Port for Other Instruments |
| Material of Construction | IS2062 Gr.B |
| Gas Stored Volume | 13 M3 |
| Corrosion Allowance | 1.5 MM |
| Water Volume | 3000 Litres |
| Gas Stored | Nitrogen/Oxygen |

| | |
|---|---|
| Design Standard | ASME Sec. VIII Div.1 Pressure Vessel Design |
| Working Pressure | 8 Barg |
| Hydrotest Pressure | 13.2 Barg |
| Accessories Included | Pressure Guage Safety Valve Manual Drain Additional Port for Other Instruments |
| Material of Construction | IS2062 Gr.B |
| Gas Stored Volume | 19.5 M3 |
| Corrosion Allowance | 1.5 MM |
| Gas Generated | Nitrogen |
| Gas Pressure | upto 6.5 Barg |
| FLOW AT 99% PURITY | 127 Nm3/Hr DRY AIR REQUIRED 164 CFM |
| FLOW AT 99.5% PURITY | 106 Nm3/Hr DRY AIR REQUIRED 159 CFM |
| FLOW AT 99.9% PURITY | 79 Nm3/Hr DRY AIR REQUIRED 150 CFM |
| FLOW AT 99.95% PURITY | 71 Nm3/Hr DRY AIR REQUIRED 157 CFM |
| COMPRESSED AIR PRESSURE REQUIRED | 7.5 Barg |
| RECOMMENDED NITROGEN STORAGE | 2000 Liters |
| POWER SUPPLY | 230 V/ 110 V 50/60 Hz Single Phase |
| RECOMMENDED AIR RECEIVER | 1500 Litres Part of Air System |
| INPUT AIR DEW POINT MONITOR | INCLUDED |
| CMS Warranty | 10 Years* |

SO Remarks

Final Remarks

**Absstem Industrial Solutions Pvt. Ltd.**
Ground Floor, Plot No. 591, Sector 8, Phase IV
IMT Manesar, Gurugram, Haryana - 122052
**Contact**: 1800 547 0506 | indsales@absstem.com
**CIN**: U29256HR2022PTC103387

# Commercial Offer

| S No | Item Code | Item Name | Qty | List Price | Discount | GST(%) | Amount |
|---|---|---|---|---|---|---|---|
| 1 | ASH74 | Vacuum Blower | 2 | 3,06,250.00 | 1,12,500.00 | 18.00 | 5,00,000.00 |
| 2 | ASH155 | 15TNLX125PSI 20HP | 3 | 8,00,000.00 | 6,00,000.00 | 18.00 | 18,00,000.00 |
| 3 | IR-15T2X20 | IR-15T2X20 | 3 | 6,50,000.00 | 6,60,000.00 | 18.00 | 12,90,000.00 |
| 4 | HPS16 | 2000 ltr HP Storage Tank 65 Barg | 1 | 8,92,500.00 | 2,82,500.00 | 18.00 | 6,10,000.00 |
| 5 | ASH321 | Refrigerated Dryer 2M3 | 1 | 2,30,000.00 | 75,000.00 | 18.00 | 1,55,000.00 |
| 6 | AIS0208ST | AI-2000L | 2 | 1,60,000.00 | 1,00,000.00 | 18.00 | 2,20,000.00 |
| 7 | AIS0308ST | AI-3000L | 2 | 2,10,000.00 | 1,20,000.00 | 18.00 | 3,00,000.00 |
| 8 | ASH311 | Low Pressure and high Pressure Pipeline | 2 | 2,00,000.00 | 90,000.00 | 18.00 | 3,10,000.00 |
| 9 | nGEN055SH | nGEN055SH | 1 | 27,86,000.00 | 12,00,000.00 | 18.00 | 15,86,000.00 |
| 10 | ASH322 | Heat Exchanger for 2m3 capacity | 1 | 1,35,000.00 | 50,000.00 | 18.00 | 85,000.00 |
| 11 | ASH313 | VFD 5 KW Auto | 2 | 30,000.00 | 10,000.00 | 18.00 | 50,000.00 |
| 12 | ASH314 | Pressure Reducing Station | 2 | 1,00,000.00 | 20,000.00 | 18.00 | 1,80,000.00 |
| 13 | ASH220 | FILTER FOR HIGH PRESSURE | 1 | 1,00,000.00 | 15,000.00 | 18.00 | 85,000.00 |
| 14 | ASH60 | N2 Mass Flow Meter | 1 | 1,75,000.00 | 66,000.00 | 18.00 | 1,09,000.00 |
| | | | | | | Sub Total | 72,80,000.00 |
| | | | | | | IGST | 13,10,400.00 |
| | | | | | | Net Amount () | 85,90,400.00 |

# Terms And Conditions

| | |
|---|---|
| 1. EXCLUSIONS & CLIENTS SCOPE | All erection / civil work, All Power Cables & Cabling out of battery limit of PSA Plant, Cable Trenches etc. Unloading / Shifting of Gas Plant at Clients site will be in Client Scope. Additional gas piping, cooling water (if required). |
| 2. P&F | NIL |
| 3. Freight | Inclusive |
| 4. Payment Terms | 50% Advance with your Prestegious Purchase Order and 40% against PI before dispatch and Balance after commissioning |
| 5. Delivery | 6-8 Weeks from the PO and Advance. Rest can be confirmed for Availability |
| 6. Scope of Supply | Nitrogen recovery plant, 80 Nm3/hr, 99.9% |



**Absstem Industrial Solutions Pvt. Ltd.**
Ground Floor, Plot No. 591, Sector 8, Phase IV
IMT Manesar, Gurugram, Haryana - 122052
**Contact**: 1800 547 0506 | indsales@absstem.com
**CIN**: U29256HR2022PTC103387