Sales Order No : S26000057

Job No : N108,N108,N108

Sales Person : Arifa Zaidi

Mobile

Consignee Details :

Standard Radiators Pvt. Ltd.

Savli Store Standard Radiators Pvt. Ltd. Survey No. 263/3 Village-Karachiya, Ta-Savli Vadodara

GUJARAT

VADODARA 391520

Sale Order Date : 07-Jul-2026

Customer Information

Standard Radiators Pvt. Ltd.

Dharmesh Mistry

Survey No. 263/3 Village-Karachiya, Ta-Savli

GUJARAT

VADODARA 391520

dharmesh@standardradiators.com

Performance

Product	Description	Make	Qty
nGen Nitrogen Generator Ultra Purity	nGEN120UH Nitrogen		1

Caption	Specification
Gas Generated	Nitrogen
Gas Pressure	upto 6.5 Barg
FLOW AT 99.99% PURITY	218 Nm3/Hr DRY AIR REQUIRED 616 CFM
FLOW AT 99.995% PURITY	196 Nm3/Hr DRY AIR REQUIRED 692 CFM
FLOW AT 99.999% PURITY	147 Nm3/Hr DRY AIR REQUIRED 692 CFM
COMPRESSED AIR PRESSURE REQUIRED	7.5 Barg
RECOMMENDED NITROGEN STORAGE	4000 Liters
POWER SUPPLY	230 V/ 110 V 50/60 Hz Single Phase
RECOMMENDED AIR RECEIVER	5000 Litres Part of Air System
INPUT AIR DEW POINT MONITOR	INCLUDED
CMS Warranty	10 Years*
Water Volume	4000 Litres
Gas Stored	Nitrogen/Oxygen
Design Standard	ASME Sec. VIII Div.1 Pressure Vessel Design
Working Pressure	8 Barg
Hydrotest Pressure	13.2 Barg
Accessories Included	Pressure Guage Safety Valve Manual Drain Additional Port for Other Instruments
Material of Construction	IS2062 Gr.B
Gas Stored Volume	26 M3
Corrosion Allowance	1.5 MM
Air Compressor KW	110 KW
Air Compressor Make	Atlas Copco/ Ingersoll Rand/ Gardner Denver/ As per Demand
Air Dryer	Included
Dry Air Storage	6000 Liters Included
Interconnecting Piping	Included
Pre filter	Included
Dry Air Generated	734 CFM
Air Pressure	7.5 Barg
POWER SUPPLY	400 V 3 Phase 50 Hz
SO Remarks	Compressor Package Details:FAS110-7 bar Base mounted Refrigerant air dryer1000 CFM
Final Remarks	Full Plant with air comp + Air Dryer + Air reciever + PSA + S.T

Absstem Industrial Solutions Pvt. Ltd.
Ground Floor, Plot No. 591, Sector 8, Phase IV
IMT Manesar, Gurugram, Haryana - 122052
Contact: 1800 547 0506 | indsales@absstem.com
CIN: U29256HR2022PTC103387

Commercial Offer

S No	Item Code	Item Name	Qty	List Price	Discount	GST(%)	Amount
1	nGEN120UH	nGEN120UH	1	91,04,000.00	31,04,000.00	18.00	60,00,000.00
2	AIS0408ST	AI-4000L	1	2,80,000.00	56,000.00	18.00	2,24,000.00
3	ACSC110F	C110F0730	1	41,50,000.00	16,43,100.00	18.00	25,06,900.00
						Sub Total	87,30,900.00
						P&F	2,61,927.00
						IGST	16,18,708.86
						Net Amount (INR)	1,06,11,535.86

Terms And Conditions

1. EXCLUSIONS & CLIENTS SCOPE	All erection / civil work, All Power Cables & Cabling out of battery limit of PSA Plant, Cable Trenches etc. Unloading / Shifting of Gas Plant at Clients site will be in Client Scope. Additional gas piping, cooling water (if required).
2. P&F	3% Extra.
3. Freight	Extra at Actuals.
4. Insurance	In your Scope.
5. Payment Terms	40% Advance with PO, 50% Before Dispatch, 10%Against commissioning.
6. Delivery	6-8 Weeks from the PO and Advance. Rest can be confirmed for Availability
7. Warranty	We hereby confirm that, our equipment shall have Suppliers warranty for a period of 12 months from the date of Commissioning or 18 months from date of Dispatch whichever is earlier.
8. GST	As per the Commercial Table.
9. Billing Details (Name & Address)	Invoice To : Standard Radiators Pvt. Ltd. Survey No. 263/3 Village-Karachiya, Ta-Savli Vadodara, 391520
10. Contact Details (Email id and Phone Number)	Email - dharmesh@standardradiators.com Contact Number - 9998947450
11. Shipping Address	Savli Store Standard Radiators Pvt. Ltd. Survey No. 263/3 Village-Karachiya, Ta-Savli Vadodara- 391520
12. GST Number	24AACCS5507K1ZD
13. Freight Scope	Client
14. Insurance Scope	Client
15. Installation and commissioning Engineer	Stay - Client scope Food - Absstem Travel - Absstem
16. Committed date of Delivery	18th August 2026
17. Scope of Supply	Type of Plant - Nitrogen etcb) Committed flow- 196Nm3/hr c) Committed Purity - 99.995% d) Committed Pressure - Standard e) Model - nGEN120UH

Additional Order Information

Field Name	Field Value
1. P&F	261927