Sales Order No : S26000058

Job No :

Sales Person : Arifa Zaidi

Mobile

Consignee Details :

rPET SSP Plant

IDCO Sahaspur, Begunia-6, Khorda, Odisha

WEST BENGAL

Sale Order Date : 07-Jul-2026

Customer Information

GASCOME ENGINEERING SERVICES

Bikram Debnath

Holding No 345/4, 96 Nandan Nagar, Belghoria

WEST BENGAL

KOLKATA

gascomengineeringservices@gmail.com

Performance

Product	Description	Make	Qty
nGen Nitrogen Generator High Purity	nGEN020SH Nitrogen		3

Caption	Specification
Gas Generated	Nitrogen
Gas Pressure	upto 6.5 Barg
FLOW AT 99% PURITY	73 Nm3/Hr DRY AIR REQUIRED 95 CFM
FLOW AT 99.5% PURITY	61 Nm3/Hr DRY AIR REQUIRED 92 CFM
FLOW AT 99.9% PURITY	45 Nm3/Hr DRY AIR REQUIRED 85 CFM
FLOW AT 99.95% PURITY	41 Nm3/Hr DRY AIR REQUIRED 90 CFM
COMPRESSED AIR PRESSURE REQUIRED	7.5 Barg
RECOMMENDED NITROGEN STORAGE	1500 Liters
POWER SUPPLY	230 V/ 110 V 50/60 Hz Single Phase
RECOMMENDED AIR RECEIVER	1000 Litres Part of Air System
INPUT AIR DEW POINT MONITOR	INCLUDED
CMS Warranty	10 Years*
Water Volume	1000 Litres
Gas Stored	Nitrogen/Oxygen
Design Standard	ASME Sec. VIII Div.1 Pressure Vessel Design
Working Pressure	8 Barg
Hydrotest Pressure	13.2 Barg
Accessories Included	Pressure Guage Safety Valve Manual Drain Additional Port for Other Instruments
Material of Construction	IS2062 Gr.B
Gas Stored Volume	6.5 M3
Corrosion Allowance	1.5 MM
Water Volume	1500 Litres
Gas Stored	Nitrogen/Oxygen

Design Standard	ASME Sec. VIII Div.1 Pressure Vessel Design
Working Pressure	8 Barg
Hydrotest Pressure	13.2 Barg
Accessories Included	Pressure Guage Safety Valve Manual Drain Additional Port for Other Instruments
Material of Construction	IS2062 Gr.B
Gas Stored Volume	9.75 M3
Corrosion Allowance	1.5 MM
Water Volume	10000 Litres
Gas Stored	Nitrogen/Oxygen
Design Standard	ASME Sec. VIII Div.1 Pressure Vessel Design
Working Pressure	8 Barg
Hydrotest Pressure	13.2 Barg
Accessories Included	Pressure Guage Safety Valve Manual Drain Additional Port for Other Instruments
Material of Construction	IS2062 Gr.B
Gas Stored Volume	65 M3
Corrosion Allowance	1.5 MM
SO Remarks	1000 Ltr Dry Air Receiver,10 Barg- 1 Nos 1500 Ltr Nitrogen Storage Tank,8 Barg- 3Nos "41 Nm3/hr, 99.95%, 6.5-7.5Brag N2 press. nGEN020SH"- 3Nos 1/2" Fine Filters, 0.01 micron- 3Nos 200 Nm3/hr, 0.01 micron Filter- 1Nos Siemens S7-1215PLC, HMI and Accessories cost difference- 3Nos SS 316L 1/8" tubing for oxygen analyzer sample- 3Nos SS Inlet Air Header from Air Receiver to ALL N2 plants- 1Nos SS Nitrogen Pipeline from PSA to N2 tanks- 1Nos 10000 Ltr Nitrogen Storage Tank,8 Barg- 1Nos N2 & Ai
Final Remarks	

Absstem Industrial Solutions Pvt. Ltd.
Ground Floor, Plot No. 591, Sector 8, Phase IV
IMT Manesar, Gurugram, Haryana - 122052
Contact: 1800 547 0506 | indsales@absstem.com
CIN: U29256HR2022PTC103387

Commercial Offer

S No	Item Code	Item Name	Qty	List Price	Discount	GST(%)	Amount
1	nGEN020SH	nGEN020SH	3	18,83,000.00	11,92,200.00	18.00	44,56,800.00
2	AIS0108ST	AI-1000L	1	1,00,000.00	44,290.00	18.00	55,710.00
3	AIS0158ST	AI-1500L	3	1,30,000.00	1,39,305.00	18.00	2,50,695.00
4	AIS1008ST	AI-10000L	1	7,20,000.00	4,13,500.00	18.00	3,06,500.00
						Sub Total	50,69,705.00
						IGST	9,12,546.90
						Net Amount (INR)	59,82,251.90

Terms And Conditions

1. EXCLUSIONS & CLIENTS SCOPE	All erection / civil work, All Power Cables & Cabling out of battery limit of PSA Plant, Cable Trenches etc. Unloading / Shifting of Gas Plant at Clients site will be in Client Scope. Additional gas piping, cooling water (if required).
2. P&F	Nil
3. Freight	Inclusive
4. Insurance	Inclusive
5. Payment Terms	5% Advance with your Prestegious Purchase Order, 80% Payment + GST Against Dispatch and Balance against PI.
6. Delivery	Before 31st March 2027
7. Warranty	We hereby confirm that, our equipment shall have Suppliers warranty for a period of 12 months from the date of Commissioning or 18 months from date of Dispatch whichever is earlier.
8. GST	As per the Commercial Table.
9. Billing Details (Name & Address)	GASCOM ENGINEERING SERVICES 96, Nandan Nagar, Basak Para, Belghoria, 24 Parganas (N), Kolkata 700083
10. Contact Details (Email id and Phone Number)	Email - gascomengineeringservices @gmail.com, Contact Number - 6289113521 , 8240491694
11. Shipping Address	rPET SSP Plant at IDCO Sahaspur, Begunia-6, Khorda, Odisha, IN.
12. GST Number	06AAWCA9492P1ZF
13. Freight Scope	Absstem
14. Insurance Scope	Absstem
15. Installation and commissioning Engineer	Absstem
16. Committed date of Delivery	Before 31st March 2027
17. Scope of Supply	Type of Plant - Nitrogen etc b) Committed flow- 41Nm3/hr- c) Committed Purity - 99.95%d) Committed Pressure - gas pressure between 6.5-7.5barg e) Model - nGEN50UH

Absstem Industrial Solutions Pvt. Ltd.
Ground Floor, Plot No. 591, Sector 8, Phase IV
IMT Manesar, Gurugram, Haryana - 122052
Contact: 1800 547 0506 | indsales@absstem.com
CIN: U29256HR2022PTC103387