Sales Order No : S26000064

Job No : N109,N109,N109,N109

Sales Person : Pramod Kumar

Mobile

Consignee Details :

Lava International Ltd.

A154D, Sector-63

UTTAR PRADESH

NOIDA 201309

Sale Order Date : 29-Jul-2026

Customer Information

Lava International Ltd.

Praveen Sharma

A154D, Sector-63

UTTAR PRADESH

NOIDA 201309

Praveen.kumar2@lavainternational.in

Performance

Product	Description	Make	Qty
Compressed Air System	C030F0205 Air System		1

Caption	Specification
Air Compressor KW	30 KW
Air Compressor Make	Atlas Copco/ Ingersoll Rand/ Gardner Denver/ As per Demand
Air Dryer	Included
Dry Air Storage	2000 Liters Included
Interconnecting Piping	Included
Pre filter	Included
Dry Air Generated	205 CFM
Air Pressure	7.5 Barg
POWER SUPPLY	400 V 3 Phase 50 Hz
Make	Atlas Copco
Model	F160 Export
Capacity	339 CFM
PDP	3 to 10 deg C
Refrigerant	R410A
Power Supply	230V/1P/50Hz
Gas Generated	Nitrogen
Gas Pressure	upto 6.5 Barg
FLOW AT 99.99% PURITY	71 Nm3/Hr DRY AIR REQUIRED 201 CFM
FLOW AT 99.995% PURITY	64 Nm3/Hr DRY AIR REQUIRED 226 CFM
FLOW AT 99.999% PURITY	48 Nm3/Hr DRY AIR REQUIRED 226 CFM
COMPRESSED AIR PRESSURE REQUIRED	7.5 Barg
RECOMMENDED NITROGEN STORAGE	2000 Liters
POWER SUPPLY	230 V/ 110 V 50/60 Hz Single Phase

RECOMMENDED AIR RECEIVER	2000 Litres Part of Air System
INPUT AIR DEW POINT MONITOR	INCLUDED
CMS Warranty	10 Years*
Water Volume	3000 Litres
Gas Stored	Nitrogen/Oxygen
Design Standard	ASME Sec. VIII Div.1 Pressure Vessel Design
Working Pressure	8 Barg
Hydrotest Pressure	13.2 Barg
Accessories Included	Pressure Guage Safety Valve Manual Drain Additional Port for Other Instruments
Material of Construction	IS2062 Gr.B
Gas Stored Volume	19.5 M3
Corrosion Allowance	1.5 MM
SO Remarks	Air Compressor - 1 No. Ref. Dryer with pre filter -1 No. Air Receiver, 2000 ltr - 1 No. Internal Piping - 1 Set Ref. Dryer with prefilter -1 No. 40 NB Angle Valve at final N2 outlet pipeline of both Plants -1 No. Power Panel for1 Comp & 2 dryer - 1 No. nGEN 80UH - 1 No. N2 Tank 3000 ltr - 2 Nos. Freight 1 Unloading & Shifting 1 Piping between existing Air Compressors and dryer with new supplied Air Compressor and dryers need to be done as working standby with all three options
Final Remarks	

Absstem Industrial Solutions Pvt. Ltd.
Ground Floor, Plot No. 591, Sector 8, Phase IV
IMT Manesar, Gurugram, Haryana - 122052
Contact: 1800 547 0506 | indsales@absstem.com
CIN: U29256HR2022PTC103387

Commercial Offer

S No	Item Code	Item Name	Qty	List Price	Discount	GST(%)	Amount
1	ACSC030F	C030F0205	1	17,55,000.00	2,80,800.00	18.00	14,74,200.00
2	ASH532	Refrigerated Air Dryer F160 AC 339 CFM	1	3,83,300.00	43,300.00	18.00	3,40,000.00
3	nGEN070UH	nGEN070UH	1	46,85,000.00	13,64,200.00	18.00	33,20,800.00
4	AIS0308ST	AI-3000L	2	2,10,000.00	52,500.00	18.00	3,15,000.00
						Sub Total	54,50,000.00
						IGST	9,81,000.00
						Net Amount (INR)	64,31,000.00

Terms And Conditions

1. P&F	Inclusive
2. Freight	Inclusive
3. Insurance	Inclusive
4. Payment Terms	50% Advance with your Prestegious Purchase Order and Balance against PI
5. Delivery	by 20th August
6. Warranty	We hereby confirm that, our equipment shall have Suppliers warranty for a period of 12 months from the date of Commissioning or 18 months from date of Dispatch whichever is earlier.
7. Scope of Supply	Nitrogen b) Committed flow - 75 Nm3/hr c) Committed Purity - 99.99% d) Committed Pressure - 6.0 Barg e) Model - nGen 80UH

Absstem Industrial Solutions Pvt. Ltd.
Ground Floor, Plot No. 591, Sector 8, Phase IV
IMT Manesar, Gurugram, Haryana - 122052
Contact: 1800 547 0506 | indsales@absstem.com
CIN: U29256HR2022PTC103387